BRUHAT BANGALORE MAHANAGARA PALIKE
EXCECUTIVE ENGINEER DASHARAHALLI DIVISION

NAME OF WORK :- Providing Pathway and Other works to Indira Kicthen Surrounding area in ward no 14

Est Cost: Rs 4.99Lakhs

Sl.No	Description of work	Mesurement Nos	L	B	D	Qty	Unit	Rate	Amount
1	KSRRB 300-2 : Earthwork excavation by manual means in Ordinary soil invovling an average horizontal throw upto 2meters and an average lift upto 1.5m. Excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. (Page no-142, Item no-19.2) including disposing of excavated earth at a lead of 9kms								
	Rate=Basic rate + 6% of B.R(area weightage) =[82.00 & {(2.50X1.28X9)+68.00}]=86.92+96.68 (A.W)=183.72/Cum								
	for Kerb	1	130.00	0.25	0.20	6.50			
						6.50	**Cum**	**183.72**	**1194.00**
2	KSRB 4 -1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, including cost of all materials, labour HOM of machinery curing complete as per specifications. Specification No.KBS 4.1, 4.2 (PWD SR 2016-17, Page No.12, Item No. 4.3)								
	below Kerb	1	130.00	0.25	0.10	3.25			
	for pathway	1	9.00	3.50	0.20	6.30			
		1	4.00	3.70	0.20	2.96			
		1	12.30	1.00	0.20	2.46			
		1	13.00	1.20	0.20	3.12			
		1	15.00	2.70	0.20	8.10			
						26.19	**Cum**	**5159.02**	**135115.00**
	Basic Rate	**4867.00**							
	AW 6%	292.02							
	Total	**5159.02**							
3	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1 :2:4 with top and bottom width 114 and 165mm respectively 400 mm high and 450mm in length finished and finished with CM 1 :3 plastering and finishing cutting including form work curing including cost of all materials labour hire charges of machinery loading and unloading lead and lift transportation etc complete.(Page No-25, Item No-5.30)								
		1	130.00			130.00	mtr		
	Basic Rate	**313.00**				289.00	No.s		
	AW 6%	18.78							
	Total	**331.78**		**Total qty.**		**289.00**	**Nos**	**331.78**	**95884.00**
4	KSRB 15-15.1 : Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. - with primer(p.No 117,I.No.15.512)PWD SR-2016-17								
		1	130.00	0.45		58.50			
	Basic Rate	**90.00**							
	AW 6%	5.40							
	Total	**95.40**		**Total qty.**		**58.50**	**Sqm**	**95.40**	**5581.00**

Scanned by CamScanner

ನಂ. EE/DD/AS/12 ದಿನಾಂಕ : 12/06/17

ರೂ. Four lakh ninety nine Thousand only.

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/TS/12 ದಿನಾಂಕ : 12/06/

ರೂ. Four lakh ninety nine Thousand only.

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned by CamScanner